

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016

Indent No.20422

SCHEDULE-B

NAME OF WORK: Maintenance of UGD in W.no.12 Shetty halli Sub division

Description of work	Unit	Qty	Rates Quoted by Contractor Venkatesh G		
			In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
2	3	4	5	6	7
Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specification & as per direction of Engineer-in-charge	Cum	379.33	320.0	Rupees Three Hundred Twenty Only	121385.60
Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specification & as per direction of Engineer-in-charge	m	237	700.0	Rupees Seven Hundred Only	165900.00
Constructing brick masonry circular type manhole 0.91m internal dia at bottom 0.91 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS : 12592, total weight cover and frame to be not less than 182 Kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machinery, complete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) complete as per specification & as per direction of Engineer-in-charge	Nos	35	14115.0	Rupees Fourteen Thousand One Hundred Fifteen Only	494025.00

Signature of the Contractor

Executive Engineer

4	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	15.75	7000.0	Rupees Seven Thousand Only	110250.00
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	136.5	260.0	Rupees Two Hundred Sixty Only	35490.00
6	Providing & Fixing SFRC Cover and frame 560mm (ID) Heavy Duty.. Material complete as per specification & as per direction of Engineer-in-charge	Each	60	1100.0	Rupees One Thousand One Hundred Only	66000.00
7	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications.. allow 60% of rate considered under item complete as per specification & as per direction of Engineer-in-charge	Cum	129.4	80.0	Rupees Eighty Only	10352.00
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specification & as per direction of Engineer-in-charge	Cum	379.33	90.0	Rupees Ninety Only	34139.70
Total Percentage						1037542.30 4.98%

ಮಹೇಂದ್ರ, ಇಂಜಿನಿಯರಿಂಗ್ ವರ್ಕ್ಸ್

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer